

Bring-up Guide

Current-limit initial power-up.

Verify rails before MCU operation.

Test E-stop before motor enable.

Run each channel with motor power isolated.